

**ARMY PUBLIC SCHOOL**  
**DHAR ROAD, PO SATTANI-182101**

([www.apsdharroad.com](http://www.apsdharroad.com))

Mob No- 9622011071

Land Line No – 01992-294867 (Civil)

Email ID: [apsdharroad@gmail.com](mailto:apsdharroad@gmail.com)

**NOTICE INVITING QUOTATIONS**  
**ARMY PUBLIC SCHOOL DHAR ROAD**

1. Principal APS Dhar Road on behalf of the Chairman APS Dhar Road invites sealed quotations from eligible vendors/firms for **Roof treatment on the school building at APS Dhar Road**. As per specifications mentioned in scope of work attached as Appendix 'A'
2. Cost of material, transportation and labour charges and applicable taxes etc. complete should be mentioned.
3. GST Number of the firm is required to be quoted.
4. Interested Firm/Vendor can visit the school on any day to clarify any query with regard to the above project.
5. Last date for submission of bids by 1600 hr on 19 Feb 2024. The sealed bids should be deposited/reach by the due date and time. The responsibility to ensure this lies with the bidder. Bids received beyond the time and date given above shall be rejected.
6. Sealed bids should be sent by registered post at the address given below so as to reach by the due date and time. No responsibility will be taken for postal delay or non-delivery/non receipt of bid documents.
7. Location of the tender Box: Army Public School, Dhar Road.
8. Address of the School is as under:-  
  
Army Public School, Dhar Road  
PO-Sattani, Pin -182101  
Jammu & Kashmir (UT)
9. This school reserves the right to change or vary any part thereof at any stage and also reserves the right to withdraw the project, should it become necessary at any stage/reject the quotations on **Technical Grounds/Incomplete Specification**.
10. TDS/Taxes will be deducted as per prevailing rules and regulations at the time of making final payment.

**SCOPE OF WORK FOR ROOF TREATMENT AT APS DHAR ROAD**

1. Providing and fixing of Black tar felt (Bituminous waterproofing membrane) sheets with bituminous compound (tarcoal) for waterproofing of terrace using other required chemicals to avoid further leakage and cover the existing crack and holes of the entire roof and laying and fixing of Aap membrane to strength the roof with a guarantee of next 10 yrs from the date of fixing also includes priming of surface with bituminous primer prior to placing of membrane. 05 layers of sheets having thickness 3 to 4mm, of approved quality as directed by school management. Job included material cost, firewood/blowtorches. Tarcoal and other related cost for installation complete job including GST.